Bruhath Bangalore Mahanagara Palike

Financial Bid Comparative Statement

Tender Notification No: EE/RRND/Tend/09/2021-22 Date: 29.10.2021

Indent No: BBMP/2021-22/RD/WORK_INDENT49195

Name of Work: Filling of potholes and road cut portions in ward no.16, Jalahalli for the year 2021-22

Sl No	Item Name	Unit	Estimate Quantity	As per PWD SR 2018-19		Rates quoted by KARIBASAPPA R		Rates quoted by S SANTHOSH KUMAR		Rates quoted by MOHAN B	
				Estimate Rate	Total Amount	Rate	Total Amount	Rate	Total Amount	Rate	Total Amount
1	Patching of deep potholes by restoring the granular base course using material confirming to WBM garde -III standards /WMM wherver necessary by manual means including trimming the pothole to the required shape and size, cleaning the pothole applying tack coat at 4 kg/10sqm over the WBM/ WMM surface including cleaning etc, and covering the surface with premixed mix seal TYPE-A 20mm thick including lead, loading unloading, rolling and finishing etc., including cost of materials, labour, HOM complete as per specifications. Complete as per standard specification. upto 150 mm thick	Sqm	3866.00	439.90	1700653.40	421.00	1627586.00	460.50	1780293.00	500.00	1933000.00
	Total Summary Amount				**1700653.40**		**1627586.00**		**1780293.00**		**1933000.00**
	% when compared to Amount (PWD SR 2018-19) as per sanctioned estimate.					**-4.30%Below**		**+4.68%Above**		**+13.66%Above**	
	Remarks					**L1**		**L2**		**L3**	

Executive Engineer
Rajarajeshwari nagar Division
BBMP

Scanned with CamScanner